



# UNT SYSTEM

*Proudly serving:*

UNT

UNT | Health Science Center

UNT | Dallas

UNT | System Administrative Office

**RFP #: RFCSP752-20-243994DH**

**SUBMITTAL DUE DATE:** August 20, 2020, 2:00 pm, local time

**TITLE: Terrill Hall MEP Renovation**

**DATE: August 12, 2020**

## Addendum #4

Please note the following clarifications are hereby made to the aforementioned RFCSP.

### Update/Change

Clarification to Questions #68 & #69

Question 68:	Will crawl space require fire sprinkler protection?
<b>Answer</b>	<b>No, the crawl space will not be protected.</b>
Question 69:	If sprinkler pipe must run through crawlspace, will heat trace be required?
<b>Answer</b>	<b>Heat trace and insulation will be required for fire protection piping routed within the crawl space. All piping within the basement will not be required to be protected from freezing.  Electrical contractor shall provide (2) 1p-20a circuits for heat trace tape in crawl space from panel LBA, circuits LBA-36 and LBA-38. Contractor shall verify with fire protection contractor exact routing of sprinkler piping. If fire sprinkler piping is not routed through crawl space, breakers will remain as spares.</b>

*-End of Addendum-*

*Denise Harpool*

*Issued by*

*8/12/2020*

*Date*

**ACKNOWLEDGEMENT:** Please acknowledge receipt of this addendum by initialing the appropriate line on the Addenda Checklist, Section 4 of the RFP.